



Modern Methods of Construction

NBCO

National Building Control Office

Welcome



Time	Topic	Speaker
09:00 – 9:30	Registration of delegates	
Morning Session		
Morning Chairperson	Mairead Phelan – Head of National Building Control and Market Surveillance Office	
09.30 – 10.00	Welcome to Modern Methods of Construction – Building Control	Mairéad Phelan - NBC&MSO
10:05 – 10.35	Methods of Construction – Overview	Éadaoin Ní Fhearghail - DHLGH
10.35 – 10.50	Short Interval	
10.50 – 11.20	Case Studies Timber Frame: Ballyogan Operational and Maintenance Depot, and Toronto and Region Conservation Authority Headquarters Project	Merrit Bucholz & Diane Harrington – Bucholz McEvoy Architects
11.25 – 11.50	NSAI – MMC Agrément Certification updates	Martin Searson - NSAI
11:55 – 12.25	Design and production of 2D & 3D MMC systems/projects	Paddy Mahon - Framespace
12:30 – 13:00	Best Practice approach for Building Control to check compliance for MMC building	John Sweeney – Meath County Council
13.05 – 13:30	Q&A	
13:30 – 14:30	Lunch	
Afternoon Session		
Afternoon Chairperson	Ronan Glynn – Pillar Head, MRIAI, NBCO&MSO	
14:30 – 15:00	Delivery of MMC Projects for large scale developments	Jason Van Hout – Glenveagh
15.05 – 15.35	Case Study -Precast Concrete Wall Panels MMC - Tallaght Development	James Matthews - Coadys
15.40 – 16:10	3D printed Concrete building: Case study Louth County Council	Conor King – Louth County Council
16:15 – 16.45	Q&A and Round Table Discussion	

<https://app.sli.do>

Modern Methods of Construction



<https://app.sli.do/event/vZL7Gx9cwH15QC6EpuLfeD>

COADY
ARCHITECTS



bucholzmcEvoyARCHITECTS




An Roinn Tithíochta,
Rialtais Aitiúil agus Oidhreachta
Department of Housing,
Local Government and Heritage



NBCO

National Building Control Office



Mairéad Phelan

INSPECTIONS EDUCATION MARKET COMPLIANCE IS-BCMS
TRAINING SURVEILLANCE SUPPORT

*An Oifig Náisiúnta um Rialú Foirgníochta agus
Faireachas Margaidh*

**NATIONAL BUILDING CONTROL AND
MARKET SURVEILLANCE OFFICE**



Framework
for
Building Control
Authorities



Version 1.1 June 2016



Stay up to date:



Google Analytics Report
2 Jan 2024 - 2 Jan vs. 31 Dec 2022 - 1 Jan 2024
NBCO / Local Government Portal - GA4

Active users ▾ by Country

Active users
57,339 +30,725 (↑ 115.45%)

	Ireland	53,168 +28,387 (↑ 114.55%)
	United Kingdom	3,087 +1,873 (↑ 154.28%)
	United States	351 +223 (↑ 174.22%)
	Spain	282 +133 (↑ 89.26%)
	France	243 +135 (↑ 125.0%)
	Germany	114 -33 (↓ 22.45%)
	Australia	128 +99 (↑ 341.38%)
	India	128 +72 (↑ 128.57%)
	Netherlands	96 +44 (↑ 84.62%)
	Portugal	91 +37 (↑ 68.52%)

[View countries](#)

Shared from the Google Analytics mobile app. 09/03/2025 10:46

Shared Service of the 31 Building Control & Market Surveillance Authorities

Compliance (Administration/Design/Construction/Maintenance)

Building Regulations

**Health, Safety & Welfare of People
in or about Buildings**

- ***“BASIC REQUIREMENTS FOR CONSTRUCTION WORKS*** Construction works as a whole and in their separate parts must be fit for their intended use, taking into account in particular the health and safety of persons involved throughout the life cycle of the works. Subject to normal maintenance, construction works must satisfy these basic requirements for construction works for an economically reasonable working life.”,

1. **Mechanical resistance and stability**
2. **Fire safety**
3. **Hygiene, health and the environment**
4. **Safety and accessibility in use**
5. **Protection against noise**
6. **Energy economy and heat retention**
7. **Sustainable use of natural resources**

DURABILITY!

Design & Construction
Administration

All Methods of Construction



NBCO

National Building Control Office

60 years

Agrément Certs
60 Years!!!

Materials & Workmanship Part D

Materials and workmanship

D1 All works to which these Regulations apply shall be carried out with proper materials and in a workmanlike manner.


D3 In this Part, “proper materials” means materials which are fit for the use for which they are intended and for the conditions in which they are to be used, and includes materials which:

- (a) bear a CE Marking in accordance with the provisions of the Construction Products Regulation;
- (b) comply with an appropriate harmonised standard or European Technical Assessment, in accordance with the provisions of the Construction Products Regulation; or
- (c) comply with an appropriate Irish Standard, Irish Agrément Certificate or with alternative national technical specifications of any State which is contracting party to the Agreement on the European Economic Area, which provides for use an equivalent level of safety and suitability

1.1 of Technical Guidance Document D – Materials and Workmanship including: -

- a. **Independent certification** schemes approved by the (NAB) e.g. (NSAI)... such certification schemes may be in addition to, but not conflict with, CE marking;
- b. **Tests and calculations carried out by an accredited laboratory** showing that the material is capable of performing the function for which it is intended.
- c. **Performance in use**, i.e. that the material can be shown by experience, such as its use in a substantially similar way in an existing building, to be capable of enabling the building to satisfy the relevant functional requirements of the Building Regulations.

Where alternative approaches are being considered, the local building control authority should be consulted at the earliest possible opportunity, to seek advice from the authority on the proposed development.





60 years

Agrément Certs
60 Years!!!

Office

Materials & Workmanship Part D-

Construction Products/Materials Protection Strategy to ensure fit for use

Materials and workmanship

D1 All works to which these Regulations apply shall be carried out with proper materials and in a workmanlike manner.

D3 In this Part, “proper materials” means materials which are fit for the use for which they are intended and for the conditions in which they are to be used, and includes materials which:

- **Damage to Materials/construction** Products to be used in Construction Is Real
- Timber, sheet goods, roof trusses, and wall panels **get left out in the rain, snow, and muck, leading to moisture-related issues**, such as warping and Mold.
- **Rain and snow also cause** the breakdown of adhesives, causing wood-based panel products to swell and delaminate.
- **Schedule materials deliveries** as close as possible to the time those materials are placed in the building & NOT sitting out in the.
- **Keep the materials under cover**—in all weather—with plastic sheeting until you need them.
- **Temporary Site Storage**—protect construction materials

D

Materials and
Workmanship

Building
Regulations
2013

Technical
Guidance
Document





60 years

Agrément Certs
60 Years!!!

Maintaining quality Control— a
planned multi-faceted approach

- **Proper Materials**,

- **Design**
- **Workmanship**
and
- **Materials**
Fit for
use/purpose in
the conditions,
location..

- **People**

- **Health**
- **Safety**
and
- **Welfare**


- **Planning**

- **clear quality standards,**
- **rigorous inspection procedures,**
- **training staff,**
- **continuously monitoring**
and
- **improving processes**
to ensure consistent quality
throughout the supply chain



Modern Methods of Construction Introductory Guide

<https://www.gov.ie/en/publication/e5e78-modern-methods-of-construction-introductory-guide/>



Introduction

This guide to Modern Methods of Construction (MMC) describes a range of innovative construction processes to deliver quality and compliant housing. This includes offsite construction techniques such as mass production and factory assembly as well as onsite innovations. Modern Methods of Construction will significantly help address Ireland's housing needs in line with Housing for All – the national strategy for housing.

This guide has six parts as follows:

1. Modern Methods of Construction (MMC)
2. The main benefits of MMC
3. The seven categories of MMC – an at-a-glance view
4. The most commonly used categories of MMC for housing
5. Quality assurance (compliance and certification) – this part is mainly for industry readers
6. Initiatives to promote MMC in Ireland

1 Modern Methods of Construction

Modern Methods of Construction is an industry term used to describe a range of manufacturing and innovative alternatives to traditional construction.

MMC can:

- help boost productivity and efficiency of housing delivery, and
- increase the environmental sustainability of new housing delivery.

2 Benefits of MMC

There are many benefits of adopting Modern Methods of Construction more widely. These include:

Faster delivery of construction projects

MMC techniques can speed up the delivery of construction projects by between 20% and 60%. Both off and onsite activity can be improved. Many of the construction processes happen offsite in factory conditions where, for example, factors such as bad weather do not disrupt delivery times.



High-quality homes

MMC promotes precision through digitalisation and strict quality-control processes. Creating construction components and units using factory-standard precision and consistency adds to the quality of structures. This means that they will achieve their intended performance and durability requirements of 60 years.



Increased sustainability

MMC strengthens quality of construction such as improving air-tightness in homes. This improves the energy performance of homes and promotes higher Building Energy Ratings (BER) resulting in improved comfort, lower energy bills and reduced carbon emissions.



MMC also helps to:

- reduce manufacturing waste and energy, as well as reducing harmful emissions in transporting components,
- improve sustainability and circularity (most efficient use of materials), and
- reduce embodied carbon (which will help us meet our carbon-neutral goals as MCC can, for example, encourage the use of lower carbon-intensive materials).

More affordable

MMC can reduce construction costs when they are combined with a steady supply of standardised designs. This can mean that new housing is more affordable for the purchaser or tenant.



More diversity in the workforce

The indoor factory environment, with regular working hours and a consistent place of work is, attractive to a more diverse and localised workforce.



Overall, greater use of MMC can boost productivity in the construction sector and open new opportunities for innovation.



Figure 1: MMC factory-controlled environment

3 The seven categories of MMC – an at-a-glance view

The seven categories of MMC are:

- Category 1** Pre-manufacturing – 3D primary structural systems (Volumetric)
- Category 2** Pre-manufacturing – 2D primary structural systems (Panelised)
- Category 3** Pre-manufacturing – non systemised primary structure
- Category 4** Additive manufacturing – (structural and non-structural)
- Category 5** Pre-manufacturing – non-structural assemblies and sub-assemblies, for example pods
- Category 6** Traditional building product-led site labour reduction and productivity improvements
- Category 7** Site process-led labour reduction/productivity assurance improvements (innovative processes and approaches)



Figure 2: Categories of MMC



Panelised components (category 2)

This MMC category uses flat panel units such as panelised walls, which can be made from a range of materials. They are made in factories and assembled onsite to produce a house or apartment.

Panelised components can include:

- walls, roof and floors,
- insulation and linings, and
- cladding, windows, roofing and doors.

They can be made from different materials such as:

- Timber Frame
- Light Gauge Steel Frame (LGSF),
- Precast Concrete Panels and Structurally-Insulated Panels (SIPs), or
- Cross Laminated Timber (CLT).



Figure 4: Panelised unit



Pre-manufacturing assemblies and sub-assemblies (category 5)

This applies to:

- partition wall systems,
- weatherproofing or insulation roofing finish assemblies, and
- non-load-bearing volumetric assemblies known as 'pods', often used for kitchens and bathrooms.



Changes to Online Assessment

Existing System

Dwelling House Type*:
- Select -

No. of Buildings of this building type*:
[Text Input]

Are the works being carried out by or on behalf of an Approved Housing Body*:
- Select -

Are the works being carried out by or on behalf of a Local Authority*:
- Select -

Type of Construction*:

- ☐ Timber Frame
- ☐ Masonry
 - ☐ Brick
 - ☐ Block
 - ☐ Stone
- ☐ Concrete
- ☐ Steel
 - ☐ Structural Steel
 - ☐ Light gauge Steel
- ☐ Other

Is the load-bearing structure pre-fabricated off-site*:
- Select -

Number of Storeys: above ground*:
[Text Input]

Number of Storeys: below ground*:
[Text Input]

Height (m) :
[Text Input]

Height of Top Floor (m) :
[Text Input]

Total Floor area of building / works (sqm)*:
[Text Input]

The type of construction used in the buildings of works. The existing system allowed for multiple types of construction within one building.

Load-Bearing Structures that arrive on site pre-fabricated, 3D modular for instance. The question was not well defined and could lead to errors.

No. of rooms*:

[Text Input]

No. of bedrooms*:

[Text Input]


No. of WC's*:

[Text Input]

Changes to Online Assessment

Proposed Improvements – 2 New Questions in the form of dropdown menus

PROPOSED CONFIGURATION



Main Method of Construction?

Selection available:


- Standard Construction (Non-MMC)
- MMC Category 1 3D Volumetric Primary Structure
- MMC Category 2 2D Panelised
- MMC Category 3 non systemised
- MMC Category 4 Additive manufacturing
- MMC Category 7 Site Process

Main material for Structural Elements?

List of 15 of the most common materials plus “other”

Changes to Online Assessment

Proposed Improvements – 2 New questions are linked



The Selection under
“What is the Main Method of Construction?”
Limits the fields in the “What is the main
material for Structural Elements?”



Changes to Online Assessment

Proposed Improvements –dropdown menus

No. of Buildings of this building type*: 1

Main Method of Construction*: - Select -

For further guidance available on this page: Modern Methods of Construction (MMC) for Commencement Notices | NBCO

Main Construction Material*: - Select -

Number of Storeys: below ground*:

Height of Top Floor (m) :

Number of Storeys: above ground*:

Main Method of Construction*:

- Select -
- Select -
- MMC Category 1 - 3D Volumetric primary structural**
- MMC Category 2 - 2D Panelised
- MMC Category 3 - non-systemised primary structure
- MMC Category 4 - Additive manufacturing
- MMC Category 7 - Site process-led labour reduction / productivity assurance improvements
- Standard Construction (Non-MMC)

Main Construction Material*: - Select -

Number of Storeys: below ground*:

Height of Top Floor (m) :

Total Floor area of building / works (sqm)*:

No. of Buildings of this building type*: 1

Main Method of Construction*: MMC Category 1 - 3D Volumetric primary structural

For further guidance available on this page: Modern Methods of Construction (MMC) for Commencement Notices | NBCO

Main Construction Material*:

- Select -
- Select -**
- Timber Frame
- Mass Engineered Timber
- Precast Concrete
- Structural Steel
- Light Gauge Steel
- Other

Number of Storeys: above ground*:

Height (m) :

Total Floor area of building / works (sqm)*:

Selecting a “Main Method of Construction”
e.g. MMC Category 1 - 3D Volumetric primary Structure
Prepopulates the “Main Construction Material”



Changes to Online Assessment

Proposed Improvements –dropdown menus

No. of Buildings of this building type*:

Main Method of Construction*:
- Select -

For further guidance available on this page: Modern Methods of Construction (MMC) for Commencement Notices | NBCO

Main Construction Material*:
- Select -

Number of Storeys: below ground*:

Height of Top Floor (m) :

No. of Buildings of this building type*:

Main Method of Construction*:
Standard Construction (Non-MMC)
- Select -
MMC Category 1 - 3D Volumetric primary structural
MMC Category 2 - 2D Panelised
MMC Category 3 - non-systemised primary structure
MMC Category 4 - Additive manufacturing
MMC Category 7 - Site process-led labour reduction / product assurance improvements
Standard Construction (Non-MMC)

Main Construction Material*:
- Select -

Number of Storeys: below ground*:

Height of Top Floor (m) :

Total Floor area of building / works (sqm)*:

Selecting a “Main Method of Construction”
e.g. MMC Category 1 - 3D Volumetric primary
Structure
Prepopulates the “Main Construction Material”

No. of Buildings of this building type*:

Main Method of Construction*:
Standard Construction (Non-MMC)

For further guidance available on this page: Modern Methods of Construction (MMC) for Commencement Notices | NBCO

Main Construction Material*:
- Select -
Masonry Brick
Masonry Block
Masonry Stone
On-site timber frame construction
On-site structural steel assembly
Reinforced Concrete
Steel and concrete composite
Other

Number of Storeys: above ground*:

Height (m) :

Total Floor area of building / works (sqm)*:

Changes to Online Assessment

Proposed Improvements – Resource Page

No. of Buildings of this building type*:

1

Main Method of Construction*:

- Select -

For further guidance available on this page: Modern Methods of Construction (MMC) for Commencement Notices | NBCO

Link under Main Method of Construction brings you a resource page

Standard Construction (Non MMC)



Modern Methods of Construction Category 1- 3D Volumetric Primary Structure



Modern Methods of Construction Category 2- 2D Panelised



Modern Methods of Construction Category 3- non systemised primary structure



Modern Methods of Construction Category 4- Additive Manufacturing



Modern Methods of Construction Category 7- Innovative site process and approaches



Modern Methods of Construction Category 7

This category of MMC uses innovative construction techniques that improve on site processes.

Main Construction Material for MMC Category 7

The most common form of MMC Cat 7 is Insulated Concrete Formwork (ICF).

If a novel form of MMC Category 7 is being used please select other and enter in the details.

Modern Method of Construction Category 4

This MMC Category uses remote, site based or final workforce based 3D printing of parts of buildings through various material based on digital design and manufacturing techniques

Main Construction Material for MMC Category 4

- Cast in situ Concrete

If a novel form of MMC Category 4 is being used please select other and enter in the details.

Changes to Online Assessment

Proposed Improvements – Construction Material - Other

No. of Buildings of this building type*:

Main Method of Construction*:
MMC Category 2 - 2D Panelised
For further guidance available on this page: Modern Methods of Construction (MMC) for Commencement Notices | NBCO

Main Construction Material*:
- Select -
Timber Frame
Mass Engineered Timber
Precast Concrete
Structural Steel
Light Gauge Steel
Structurally Insulated Panels
Other

Number of Storeys: above ground*:

Height (m) :

Total Floor area of building / works (sqm)*:

No. of Buildings of this building type*:

Main Method of Construction*:
MMC Category 2 - 2D Panelised
For further guidance available on this page: Modern Methods of Construction (MMC) for Commencement Notices | NBCO

Main Construction Material*:
Other

Number of Storeys: above ground*:

Height (m) :

Total Floor area of building / works (sqm)*:

Main Construction Material (Other)*:
Insulated Structural Aluminium Panels

Number of Storeys: below ground*:

Height of Top Floor (m) :

If "Other" is selected then a free Text box will appear to let the Notice Creator enter concise details of proposed Material



Changes to Online Assessment

Proposed Improvements – Legacy v Proposed Change

My Notices

Use the tabs below to create and/or view your Notices and/or Certificates.

My Dashboard

My Details

My Notices
+ New notice

My Applications
(Beta mode)
+ New Application

My Certificates
+ New certificate

Search the full
Statutory Register

Logout

Project
Particulars

Online
Assessment

Phasing

Nominate
Roles

Statutory
Documents

Supporting
Documents

Payment

Building Identifier	Purpose group	Sub group	Quantity	Construction type	Options
Apartment Block	Residential (Dwellings)	Dwelling - Apartment(s) / Flat(s)	1	Masonry, Block, Concrete	View

Summary

Fee	Total No. of Apartment/Maisonette Units	Total No. of Dwelling Units	Total No. of Buildings
25,000.00	40	40	1

Legacy Projects will still display the (Legacy)
“Construction Type” under Online-Assessment

My Notices

Use the tabs below to create and/or view your Notices and/or Certificates.

My Dashboard

My Details

My Notices
+ New notice

My Applications
(Beta mode)
+ New Application

My Certificates
+ New certificate

Search the full
Statutory Register

Logout

Project
Particulars

Online
Assessment

Phasing

Nominate
Roles

Statutory
Documents

Supporting
Documents

Payment

Building Identifier	Purpose group	Sub group	Quantity	Construction type	Options
1 Detached 2 Storey Dwelling	Residential (Dwellings)	Dwelling house(s)	1	MMC Category 1 - 3D Volumetric primary structural	View

Summary

Fee	Total No. of Apartment/Maisonette Units	Total No. of Dwelling Units	Total No. of Buildings
30.00	0	1	1

New Project will display the new “Main Method
of Construction” under Online Assessment



Changes to Online Assessment

Proposed Improvements – Change to Sugar CRM – BCA's interface

Residential (Dwellings) - Dwelling house(s)

Sub Group **
Dwelling house(s)
Dwelling House Type
Detached
No. of Buildings of this building type **
30
Are the works being carried out by or on behalf of an Approved Housing Body? **
No
Are the works being carried out by or on behalf of a local authority? **
Yes
(Old) Type of Construction **
Timber
(Old) Is the load-bearing structure pre-fabricated off-site? **
No
Number of Storeys: below ground **
0
Height (m)
3.50
Total floor area of building / works (sqm) **
30.00
No. of Bedrooms **
2

Are the works being carried out by or on behalf of a local authority? **
Yes
(Old) Type of Construction **
Timber
(Old) Is the load-bearing structure pre-fabricated off-site? **
No
Number of Storeys: below ground **
1
Pre MMC Cutover
☒
Height of Top Floor (m)
3.40
No. of Rooms **
3
No. of WC's **
3

Legacy Projects will only display “(Legacy) Type of Construction” and “(Legacy) Is the load-bearing structure pre-fabricated off-site?” Under Online-Assessment

Residential (Dwellings) - Other - Residential (Dwellings)

Building Projects
NBCO CCC DIP Testing 2025 CNwCD NOR 1
Building Name / Brief Description **
3 Semi Detached- Type A
+ FSC No. (if applicable)
Type of Building or Works **
Construction of a new building(s)
Proposed use of building **
Residential (Dwellings)
Sub Group **
Other - Residential (Dwellings)
No. of Buildings of this building type **
3
What is the main method of construction? **
MMC Category 1 - 3D Volumetric primary structural
What is the main construction material for structural elements? **
Timber Frame
+ Construction Material (Other)
Number of Storeys: below ground **
0
Height (m)





Site
SR0352859
Does the building/works involve a protected structure or national monument? **
No
+ DAC No. (if applicable)
Number of Storeys: above ground **
3
Pre MMC Cutover
☐
Height of Top Floor (m)

New projects will only display the 3 New fields:
“Main Method of Construction”
“Main Construction Material” and “Other” if applicable 18

Standard Construction –Non MMC

Standard Construction – Generally Masonry Construction – as described in TGDs for a non-complex building

- Check if building details are in accordance with TGDs, these are prima facie compliance
- Check if materials are accordance with Part D
- Check if material are properly stored
- Check works are progressing in workmanlike manner
- Check if details are in accordance with ACDs



MMC Category 1 -3D Volumetric Primary Structure

Pre-manufacturing (3D primary structural systems)

Can be stand alone units, individual apartments or rooms/combination of rooms.

These are three-dimensional units consisting of floor, wall and roof panels, which are the primary structure of all or part of the building. The units are made in factories and transported to site.

- Check on site protection (Part D)
- Check Agrément Cert
- Check Factory Inspection records
- Check interface with founds (Part C)
- Check sealing between units
- Check external envelope Walls, Roofs and Balcony junctions



1
Pre-manufacturing (3D primary structural systems)

Volumetric housing units (category 1)
These are three-dimensional units and are made in factories. They are then delivered to site where they are installed.




Figure 3: Volumetric unit

The units' level of finish can vary from a basic structure to one with all services installed, ready to "plug and play".

The category includes structural framing with roofing. The category comes:

- with or without cladding (an external surface to protect buildings such as block with plaster to prevent against ingress of water from rain), and
- with or without internal fit-out such as kitchens or bathrooms.

Several volumetric units can be combined to make up a building, or a single volumetric unit can be a small dwelling. They can also be combined with other forms of construction such as pre-manufactured roofs or bathroom units (pods).

MMC Category 2- 2D Panelised (Flat-Pack!!)

- **Pre-manufacturing (2D primary structural systems)**
- *These are two-dimensional flat panel units such as panelised walls, which are part of the primary structure of the building. They are made in factories and assembled on site, to produce a building.*
- Check Agrément Cert/IS 440 compliance for Timber Frame construction
- Check On-site Protection (Part D)
- Check Factory Inspection records
- Check interface with founds
- Check sealing between units; Fire Barriers
- Check external envelope Walls, Roofs and Balcony junctions



2
Pre-manufacturing
(2D primary structural systems)

Panelised components (category 2)
This MMC category uses flat panel units such as panelised walls, which can be made from a range of materials. They are made in factories and assembled onsite to produce a house or apartment.

Panelised components can include:

- walls, roof and floors,
- insulation and linings, and
- cladding, windows, roofing and doors.

They can be made from different materials such as:

- Timber Frame
- Light Gauge Steel Frame (LGSF),
- Precast Concrete Panels and Structurally-Insulated Panels (SIPs), or
- Cross Laminated Timber (CLT).





Figure 4: Panelised unit'

MMC Category 3 - Non-Systemised Primary Structure

Pre-manufacturing components (non-systemised primary structure)

“These are two-dimensional components such as beams and posts, which form part of the primary structure of a building. They are made in factories and assembled on site to produce a building”

- Check Agrément Cert/basis of compliance
- Check On-site Protection (Part D Materials?)
- Check Factory Inspection records
- Check interface with foundations (gap details)
- Check external envelope Walls, Roofs and Balcony junctions



Pre-Manufacturing components (category 3)
This MMC Category uses pre-manufacturer structural members made of framed or mass engineered timber, cold rolled or hot rolled steel or pre-cast concrete

Structural members
Can include:

- Load Bearing Beams
- Columns
- Walls
- Core Structures
- Slabs

They can be made
From different
materials such as:

- Structural Steel
- Mass Engineered Timber
- Precast Concrete



MMC Category 4- Additive Manufacturing

Additive manufacturing (structural and non-structural)

3D printing

Additive manufacturing, also known as 3D printing, is a process that creates three-dimensional objects by adding material layer by layer.

MIT - Massachusetts Institute of Technology

https://youtu.be/_K1C_dkZK98

- Check Agrément Cert/basis of compliance
- Check On-site Protection (Part D)
- Check interface with foundations
- Check installation of ancillary items; Cavity barriers, Fire Barriers
- Check dockets/slump test/cube tests for concrete



Additive manufacturing (category 4)

This MMC Category uses remote, site based or final workforce based 3D printing of parts of buildings through various material based on digital design and manufacturing techniques

Printed Elements can include:

- Walls
- Internal Partitions

They can be made from:

- In-Situ Concrete



MMC Category 7- Site-Process led labour Reduction

Site process led site labour reduction / productivity / assurance improvements

“This includes innovative processes on the construction site such as insulated concrete formwork, which form part of the primary structure of the building.”

- Check Agrément Cert/basis of compliance
- Check horizontal damp proof course must be appropriate for the type of ICF system.
- Check joints between the windows and doors and the surrounding cladding system, sufficiently sealed and to Manufacturer’s instructions.
- Check detailing and construction of any lean-to/flat roof abutments, parapets or balcony constructions to determine how water penetration will be prevented.



7
Site process led site labour reduction / productivity / assurance improvements

Innovative site processes and approaches (category 7)
This includes drones, robotics, and insulated concrete formwork. These methods improve onsite construction.


Gap between layers


Gap between layers now filled

Figure 5 (left): The external wall of an Irish house under construction onsite. It uses Insulated Concrete Formwork (ICF). The builders will fill the gap between the two layers with reinforced concrete.

Figure 6 (right): View of this external wall after the reinforced concrete has filled the gap, using Insulated Concrete Formwork (ICF) onsite.

This category of MMC uses innovative construction techniques that improve on site processes.

Examples of category 7 MMC include:

- weatherproofing,
- standardised works (such as insulated concrete formwork – a mould to form and pour concrete),
- virtual models of buildings (Building Information Modelling (BIM)),
- using technology such as augmented and virtual reality to visualise planned and final works,
- digital tools such as robotics, drones, driverless cranes and diggers.

Compliance

Completed Building or works must be in compliance with Parts A-M of the Second Schedule of the Buildings Regulations.

For novel approaches, outside the scope of the TGDs, compliance may be demonstrated by:

- Agrément Certification
- Drawings, Calculations and Testing that demonstrates compliance

Compliance with the Building Regulations must be considered holistically, not just on the performance of constituent parts.

Those involved in the design and construction of a building may be required to provide such evidence as is necessary to establish that the requirements of the Building Regulations are being complied with.

5 Compliance

Modern Methods of Construction must be high quality.



Figure 7: Completed 2D panelised system using Timber Frame

All new buildings must comply with Irish Building Regulations and Building Control regulations. For new dwellings, all key elements must have a durability of at least 60 years.

You will find more information about Building Regulations on the Department of Housing, Local Government and Heritage website. This website also contains information on regulations for the design and construction of a new building or an extension to an existing building:

<https://www.gov.ie/en/publication/1d2af-building-regulations/>

The Building Regulations (Part D) requires that all works should be carried out with proper materials and in a workmanlike manner.

'Proper materials' means materials which are fit for the use for which they are intended, and for the conditions in which they are to be used.

Follow the link below for full Building Regulations Technical Guidance Documents. They are available on the Department of Housing, Local Government and Heritage website:

<https://www.gov.ie/en/collection/d9729-technical-guidance-documents/>

Compliance - MMC

Agrément Certification of MMC

Innovative systems such as MMC must comply with the Building Regulations. The process of Agrément certification applies to those products and processes which do not fall within the scope of existing construction standards, either because they are innovative or because they deviate from established norms.

The National Standards Authority of Ireland (NSAI Agrément) assesses, specifies testing, and where appropriate, issues **Agrément certificates**. This certificate confirms that new building products, materials, techniques and equipment are safe and fit for purpose in accordance with the Irish Building Regulations and with the terms of the certificate.

Certification

The NSAI offers certifications on the construction and sign-off stages for MMC products and building system installation compliance under building regulations.

<https://www.nsai.ie/certification/agreement-certification/modern-methods-of-construction-certification/>

NSAI also published the Agrément Guide for Modern Methods of Construction under the Housing For All plan, which can be viewed at the following link:

https://www.nsai.ie/images/uploads/certification-agreement/Guide_to_Agr%C3%A9ment_Certification_for_MMC.pdf

You can find a list of Agrément certified MMC systems here by selecting "Building Systems":

<https://www.nsai.ie/certification/agreement-certification/search-agreements-certificates/>



The system has not been assessed for use with timber frame or steel frame construction. The system can be used on NSAI Agrément certified ICF (Insulated Concrete Formwork) systems.

4.5 DURABILITY

Buildings based on the Amvic ICF System, when rendered using the Wetherby or other NSAI Agrément certified renders for use onto EPS, subject to maintenance, when constructed in accordance with the manufacturer's instructions and this Certificate, will have a minimum design life of at least 60 years in accordance with BS 7543:2015 *Guide to durability of buildings and building elements, products and components*.

External render systems can last in excess of 40 years in accordance with BS 7543:2015 subject to normal use, regular inspection and maintenance. It is important to note that the

durability of the render system is entirely dependent on the correct installation of the product in accordance with its NSAI Agrément Certificate, the manufacturer's instructions, IS EN 13914-1:2016 *Design, preparation and application of external rendering and internal plastering - Part 1: External rendering and ongoing care and maintenance as described in Section 4 of their NSAI Agrément Certificates*. Critical details include rendering at window sills, raised features, junctions with eaves and verges, and the use of suitably designed overhangs and flashings. Reference should be made to IS EN 13914-1:2016 for general advice on design, in particular on the use of angle, stop and movement joint beads.

4.6 MAINTENANCE

The rendering/concrete in the wall panels is maintenance free. However, the coloured rendering may discolour with time. It is considered that periodic re-coating of the silicone top coat may be necessary every 18 to 20 years to improve the appearance. The external sealants

Compliance - MMC



Remove forms at openings, cutting 25mm smaller to allow for adjustments. The inside of the opening is lined with 50mm x 150mm treated timber frame glued/screwed into position and propped/braced as required.

2.4.5 Reinforcement Placement

Horizontal reinforcement can be placed in different locations across the concrete fill void using the form tie/spacer toothed slots. Horizontal reinforcing bars for lintels must be located within the lintel as specified in the structural design, the minimum length of bar will be specified by the chartered structural engineer to ensure that adequate anchorage has been allowed for either side of an opening. Vertical reinforcement can then be secured to horizontal reinforcement at required centres using standard fixing methods. Bar lapping lengths as per I.S. EN 1992-1-1[7] should be adopted. The system

requires that in plain walls horizontal reinforcement be provided in top and bottom courses of every wall lift. The reinforcement is checked to ensure there is adequate concrete cover for protection and that compaction can take place. The horizontal and vertical reinforcement shall be specified by the chartered structural engineer (see Section 3.1.1).

2.4.6 Bracing

The bracing system is installed following installation of the third or fourth course of forms. Temporary bracing and propping during construction is essential to maintain alignment and adequate lateral stability during concrete filling. The installer is responsible for ensuring the adequacy of all temporary bracing. As a minimum, the full height of the assembled formwork system must be supported 700mm from corners and along the length of each wall at maximum horizontal centres of 1.8m.

All lintels must be adequately supported until the concrete has attained its minimum working strength. On exposed sites or in adverse weather conditions further support may be necessary. Typically, the bracing and alignment systems are placed on one side of the formwork (usually the inside face) during construction, however for very long or walls greater than one storey height, bracing on two sides is recommended.

